

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 081

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 1 W	A-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 NOV -2 AM 10:13
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson in a field survey on July 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO 2/9 & 131: John Mullet, 1840: Set $\frac{1}{2}$ Sec. Post-Beech 10" S 23°W 25 lks (16.5'), Beech 10" N 42°E 23 lks (15.2').
 CSR 2/260: G.F. DeLaMater, 1925: Found both Gov' B's & P, $\frac{1}{2}$ "x30" deformed bar at corner-Large Stone N 27°E 57.5'.
 CSR 2/440: G.F. DeLaMater, 1931: Added Concrete Monument S 45 $\frac{1}{2}$ °E 48.0'.
 CSR 3/284: S.O. Thorsen, 1953: Placed $\frac{3}{4}$ "x48" bar in corner-Found Concrete Monument S 45 $\frac{1}{2}$ °E 48.0'.
 LCR 2/62: G.R. McKelvey, 1977: Found $\frac{1}{2}$ " Iron Rod, fits measurements in County Surveyor's Record-nail P.Pole S 26°E 89.18', tag 12" Maple S 25°W 123.86', Plow Shoe S 27°W 41.75', Plow Shoe N 5°W 127.85'.
 Misc. Records: C.I. Robinson, 1980: Set Otsego County Monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Otsego County Monument (4" extendable) replaced with 2 $\frac{1}{2}$ " standard Otsego County Monument, 5" deep & 3"± west of centerline of gravel road, McKelvey's P.Pole & Maple.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Otsego County Monument in corner is accepted as a careful and faithful perpetuation of the position of the original corner-spike 7" Maple S 80°E 111.55', MDSH tag P.Pole S 23°E 89.50', spike 12" Maple S 31°W 123.92', 3/4"x48" iron rod N 27°W 44.50'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer
 Group, pursuant to Act 345, PA 1990.
 8/3/95 [Signature]
 Date Vice-Chairman

Signed by [Signature]
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

Date July 18, 1995