

# SURVEY & REMONUMENTATION

APR 25 1995

For corners in  
**COMMISSION**  
(County)

OTSEGO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE LIBER 0004 PAGE 049  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
94 DEC 29 PM 1:32  
EVELYN H. PRATT  
CLERK / REGISTER OF DEEDS

	Located In:	Corner Code #
1. Public Land Survey	T <u>31</u> N R <u>1</u> W	A-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											


I, Carl I. Robinson, in a field survey on December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 2/8 & 9: J. Mullett, 1840: Set Post-Beech 14" N 2°E 21 lks (13.9'), Sugar 10" S 29°W 13 lks (8.6').  
 CSR 2/260: G.F. DeLaMater, 1925, Found one Gov't B. & P., set 1/2"x30" Bar-Stone N 43°W 51.4', Elm 4" S 74°E 21.6'.  
 Concrete Monument S 43°E 51.7' added later. (Note: OCRC set monument box per 1967 Construction Plans).  
 LCRC 2/62: G.R. McKelvey, 1977: Found 1/2" iron rod in mon box and Concrete Monument S 43°E 53.74', NE Corner Fr. Garage S 40°W 119.40', NE Corner of Chimney on Cabin S 37°E 104.0', Nail P. Pole N 51°E 47.38'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 5/8" Iron Rod in Monument Box 0.5'± south of pavement centerline and on approximate centerline of gravel road north & south, DeLaMater's concrete monument, and all McKelvey's witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 5/8" Iron Rod in Monument Box 0.5'± south of pavement centerline and on approximate centerline of gravel road north & south, and is accepted as a careful and faithful perpetuation of the position of the original corner-spk P. Pole N 51°E 48.18', Concrete Monument S 43°E 53.71', NE corner of Chimney on Cabin S 37°E 104.04', 1/2" Capped Iron Rod S 53°W 46.89'.



OTSEGO COUNTY REMONUMENTATION  
 Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
 12/22/94 Date [Signature]  
 V. Chairman

Signed by [Signature]  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390 Date December 21, 1994