

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 94

For corners in

<u>OTSEGO</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>31</u> N R <u>3</u> W	D-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY,
 MICHIGAN
 RECEIVED FOR RECORD
 95 NOV -3 PM 1:38
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


I, Carl I. Robinson, in a field survey on October 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO 2/286: Austin Burt, 1850: Set Qr. Sec. Post-Maple 14" S 49°E 19 lks (12.5'), Maple 7" N 30°W 32 lks (21.1').
 CSR 1/6: A.A. Fordick, 1879: Found Gov't Post-new witness Pine stump 36" N 22°E 58 lks (38.3').
 CSR 1/15: J.M. Sanborn, 1882: Maple 14" S 49°E 19 lks (12.5'/GLO), Maple 18" N 55°W 49 lks (32.3').
 CSR 2/70: D.M. Hoffman, 1902: Pine stump 36" N 44°E 57 lks (37.6'), Hemlock 12" S 21°W 81 lks (53.5').
 CSR 2/284: G.F. DeLaMater, 1923: Found stake with stones around it, Placed Concrete Monument-Concrete Monument S 45°E 48.0', Concrete Monument S 45°W 48.0'.
 LCRC 1/11: C.E. Ostling, 1972: Found spike- Concrete Monument S 45°E 48.0', Concrete Monument S 45°W 48.0'.
 LCRC 1/151: W.W. Wakenhut, 1972: Found large spike-form spk & washer in P.Pole N 40°E 81.01', Concrete Monument S 45°E 48.10', ½" iron N 60°W 68.34'-about 1' NE of road sign.
 LCRC 2/87: P.E. Chenard, 1978: ½" iron bar-P.Pole N 41°E 81.00', Concrete Monument S 45°E 48.00', ½" capped iron rod S 50°W 51.86'.
 Misc.: C.I. Robinson, 1980: Replaced ½" iron rod with Otsego County Monument-spk P.Pole N 50°E 81.09', Concrete Monument S 45°E 48.1', spk 13" W. Birch S 50°W 67.97', spk 10" S. Maple N 60°W 77.00'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Otsego County Monument at the extended intersection of the centerlines of bituminous pavement east & south, DeLaMater's Monument SE, Wakenhut's P.Pole & iron NW, Chenard's iron SW, and Robinson's Maple & Birch.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Otsego County Monument at intersection of centerlines of bituminous pavement east & south as extended, accepted as a careful and faithful perpetuation of the position of the original corner-form nail & washer P.Pole N 40°E 81.01', Concrete Monument S 44°E 48.10', capped Iron Rod S 50°W 51.90', spk 14" Birch S 70°W 67.83', spk 15" Maple N 68°W 76.64', capped Iron Rod N 62°W 68.24'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group pursuant to Act 345, PA 1990.
 Date 11/3/95 Donald E. Swan
 V. Chairman

Signed by Carl I. Robinson
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

October 19, 1995