

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

LIBER 0004 PAGE 097

Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

For corners in

OTSEGO (County)	Located In:	Corner Code --
1. Public Land Survey	T 31 N R 3 W	E-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 NOV -3 PM 1:39
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on October 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 2/283: Austin Burt, 1850: Set Qr. Sec. Post-Sugar 10" S 18°E 20 lks (13.2'), Sugar 14" N 33°W 14 lks (9.2').
- CSR 1/21: J.M. Sanborn, 1883: Birch 10' N25°E 16 lks (10.6'), Sugar 30" S 42°W 16 lks (10.6').
- CSR 2/22: D.M. Hoffman, 1900: Sugar 24" S 71°E 53½ lks (35.3'), Sugar 8" N 34°E 14 lks (9.2').
- CSR 2/284: G.F. DeLaMater, 1933: Fence Post in corner, 1936: Fence Post removed, ½"x36" bar in corner-Elm 12" North 44.3', Linn 14" S 38°E 84.0'.
- CSR 3/298: S.O. Thorsen, 1954: ½"x36" bar under N & S fence, old B's rotted out-Elm 14" North 8.4', Elm 7" N 78°W 19.6'
- LCRC 2/167: C.I. Robinson, 1980: Fd. ½"x36" bar under N & S fence & both Thorsen's Elms (dead), Set Otsego County Monument- spk P.Pole S 85°E 59.21', spk 6"x8" Fe.Post South 0.95', spk 6"x8" Fe.Post South 17.21', spk 10" Fe.Post West 17.79'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found base of broken Otsego County Monument 1'± west of intersection of fence lines N & S and E & W, remains of Thorsen's Elm north; Robinson's P.Pole SE, & fence posts south & west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced Otsego County Monument 1'± west of intersection of fence lines N & S and E & W, accepted as a careful and faithful perpetuation of the position of the original corner-spk 7"x9" Fe. Post North 33.62', spk P.Pole S 70°E 59.00', spk 7"x9" Fe.Post South 30.84', spk 9" Fe.Post West 18.19'.



OTSEGO COUNTY REMONUMENTATION
 Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 11/2/95 Donald E. Segan
 Date V. Chairman

Signed by Carl I. Robinson
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

Date October 19, 1995