

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 126

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 DEC -6 PM 1:29
 EVELYN B. PRATT
 CLERK / REGISTER OF DEEDS

For corners in

<u>OTSEGO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 3 W	F-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	F
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


I, Carl I. Robinson, in a field survey on October 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration.
 GLO 2/286: Austin Burt, 1850: Set Qr. Sec. Post-Beech 7" S 23°E 19 lks (12.5'), Beech 6" N 58°W 23 lks (15.2').
 CSR 2/22: D.M. Hoffman, 1900: Gov't B's O.K.
 CSR 2/318: G.F. DeLaMater, 1938: Found corner O.K.- Concrete Monument S 45°W 48.0', Concrete Monument N 45°W 48.0'.
 CSR 3/438: Wm.R. Downey (MSHD), 1959: Found ½" Rod-T.Pole S 52°E 50.84', T.Pole S 22°W 76.43', T.Pole N 20°W 50.84'.
 LCRC 1/163: C.I. Robinson, 1972: Found ½" Iron Rod in pavement-tag P.Pole S 40°E 51.79', Stop Sign Post S 70°W 53.67'. P.Pole N 40°W 42.85'.
 LCRC 2/289: J.L. Schwandt, 1982: Found ½" bar and all Robinson's references, set Otsego County Monument- P.Pole S 40°E 51.79', Stop Sign Post S 70°W 53.67', Concrete Monument N 45°W 48.78', P.Pole N 40°W 42.85'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Otsego County Monument at surface and intersection of centerlines of bituminous pavements, DeLaMater's Concrete Monument (bent) northwest, subdivision monument southwest and all of Robinson's & Schwandt's references.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Otsego County Monument at intersection of centerlines of bituminous pavements, accepted as a careful and faithful perpetuation of the position of the original corner-tag (#16390) P. Pole S 50°E 52.05', tag (#26466) P.Pole S 40°W 41.39', Concrete Monument S 45°W 46.81', tag (#16390) P.Pole N 40°W 42.62'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Surveyor Peer Group, pursuant to Act 345, PA 1990.
11/27/95 Date David E. Szymanski V. Chairman

Signed by Carl I. Robinson
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

Date November 15, 1995