

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

LIBER 0004 PAGE 129

For corners in

OTSEGO <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 3 W	G-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD**

95 DEC -6 PM 1:29

FRANKIE FRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on October 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


GLD 2/272: Austin Burt, 1850: Set Qr. Sec. Post-Sugar 14" S 29°E 11 lks (7.3'), Sugar 7" N 55°W 16 lks (10.6').
 CSR 1/49: A.W. Bates, 1890: Found Gov't B & P-Sugar 16" N 84°W 40½ lks 26.7', Sugar 18" S 54°E 78 lks (51.5').
 CSR 2/534: G.F. DeLaMater, 1934: Found both B's, no P, Strap Iron in corner-Elm 10" N 33°W 25.8', Sugar 6" S 64°W 13.4'.
 LCRC 1/155: W.W. Wakenhut, 1972: Found "X" in Concrete Post (MSHD R/W marker) & DeLaMater's Sugars-spk Tree S 65°E 22.06', spk Tree S 5°E 33.48', 6" Sugar S 64°W 13.4', spk 10" Elm N 33°W 25.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found MSHD Concrete R/W Marker & Strap Iron, DeLaMater's Sugar & Elm (stump) and Wakenhut's trees (Maples).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete MSHD R/W marker & strap iron at old corner of fence to north & east, accepted as a careful and faithful perpetuation of the position of the original corner-spk N side 18" Maple S 65°E 21.80', PK W.Root 24" Maple S 10°E 33.48', spk W side 20" Maple S 65°W 13.85', nail 12" Maple N 55°W 19.25'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

11/27/95 Donald E. Sagan
Date V. Chairman

Signed by Carl I. Robinson
Surveyor's Michigan License No. 16390

Date November 18, 1995