

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

LIBER 0004 PAGE 131

Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

For corners in

OTSEGO (County)	Located In:	Corner Code --#
1. Public Land Survey	T 31 N R 3 W	G-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 DEC -6 PM 1:30
 EVELYN H. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on October 25, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


GLO 2/277: Austin Burt, 1850: Set Qr. Sec. Post-Sugar 22" S 50°E 4 lks (6.1'), Sugar 11" N 18°W 13 lks (8.6').
 CS 189/103: G.R. McKeivey, 1974: Used mathematical location on line between G-7 & G-9 on extension of fence line to west for survey in SE ¼ of Section 22, no point was set at corner.
 Misc. Field Notes: R.F. Mitchell, 1995: Set ½" iron rod on line between G-7 & G-8 on extension of fence line to west (2,628.85' to G-7 & 2,619.86' to G-9) concurrent with reconstruction of road. Contractor set Monument Box-½" iron rod N 47°E 52.5', ½" iron rod S 65°E 43.80', Steel Gate Post N 65°W 95.7', spk N. side P.Pole N 45°W 94.77'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" Iron Rod in Monument Box in centerline Old 27 North pavement on extension of fence line from west and all Mitchell's references. Mitchell and I agreed to place this corner on line between G-7 & G-9 at the fence line west to best represent the most probable location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found ½" Iron Rod in Monument Box in centerline of Old 27 North pavement on extension of fence line from west, accepted as a careful and faithful reestablishment of the position of the original corner-½" Iron Rod in sideslope N 41½°E 52.53', ½" Iron Rod S 67°E 43.80', Steel Gate Post N 66°W 95.7', spk N side P.Pole N 50°W 95.50'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 11/27/95 Donald E. Soyars
 Date V. Chairman

Signed by Carl I. Robinson Date November 21, 1995
 Surveyor's Michigan License No. 16390