

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 134

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 3 W	G-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

95 DEC -6 PM 1:30

LYLLYN A. PRATT
 CLERK/REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	13	12	11	10	9	8	7	6	5	4	3	2	1
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, Carl I. Robinson, in a field survey on October 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
 GLO 2/277: Austin Burt, 1850: Set Post-Sugar 14" S 66°E 32 lks (21.1'), Beech 8" N 64°W 11 lks (7.3').
 CSR 2/22: D.M. Hoffman, 1900: Gov't B's O.K.
 CSR 2/322: G.F. DeLaMater, 1936: 1/2"x30" bar in Monument Box (placed by MSHD)-Concrete Monument N 71°E 100.0', Concrete Monument S 70°E 100.0'.
 LCRC 1/47: W.W. Wakenhut, 1972: Found 1/2" iron in Monument Box & DeLaMater's Monument NE-Concrete Monument N 80°E 99.89', spk P.Pole N 45°E 103.53', spk 12" Maple N 15°W 108.65'.
 LCRC 1/163: C.I. Robinson, 1972: Found 1/2" iron in Monument Box at approximate intersection of pavement centerlines-tag 20" Elm S 24°E 73.20', tag P.Pole N 56°W 117.21', tag 12" S.Maple N 22°W 108.60'.
 NOTE: Corner & witnesses used in numerous surveys by several different Surveyors in the past 23 years.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Rod (9" deep) in Monument Box at intersection of pavement centerlines north-south & east-west, DeLaMater's Concrete Monument NE, Wakenhut's P.Pole NE and Robinson's P.Pole NW.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Raised 1/2" Iron Rod with capped 1/2" Iron Pipe in Monument Box at intersection of pavement centerlines north-south & east-west, accepted as a careful and faithful perpetuation of the position of the original corner-spk P.Pole N 53°E 106.47', Concrete Monument N 70°E 100.15', spk P.Pole S 67°W 90.87', tag (#16390) P.Pole N 50°W 116.98'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

11/27/95 Donald E. Sugar
 Date V. Chairman

Signed by Carl I. Robinson
 Surveyor's Michigan License No. 16390

Date November 21, 1995