

OTSEGO COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**

LIBER 0004 PAGE 99

Filing Requirement of Act 74, Mich. P.A. 1970  
 ALSO Act 345, PA 1990

For corners in

| OTSEGO<br>(County)                    | Located In:             | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey                 | T 31 N R 3 W            | G-12          |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 95 NOV -3 PM 1:39  
 EVELYN M. PRATT  
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Carl I. Robinson, in a field survey on September 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 2/277: Austin Burt, 1850: Set Qr. Sec. Post-Beech 8" East 33 lks (22.0'), Sugar 8" S 64°W 29 lks (19.3').
- CSR 2/322: G.F. DeLaMater, 1921: 2" Concrete with (illegibly?) center 20' E & W, corner is exactly in center of pavement-Elm 4" S 87°E 48.2', Elm 6" N 89°W 64.4', Gas Pipe East 25.25' & West 24.95'.
- CSR 2/318: G.F. DeLaMater, 1936: Copper tack in 2" Square Cedar plug in Concrete Pavement.
- LCR 1/47: W.W. Wakenhut, 1972: Found 1/2" Iron 0.3' down, spk T & P. Pole N 50°E 31.86', spk P. Pole N 35°W 30.51'.
- Misc.: C.I. Robinson, 1988: Found 1/2" iron in 2" square hole in old concrete, Set Otsego County Monument.
- Misc. C.I. Robinson, 1989: Removed Otsego County Monument while constructing 30" Storm Sewer crossing. Set PK nail in centerline of Pavement North 33.13', Wakenhut's witnesses undisturbed. Set PK nail in corner in 1990 because N. Center Street was proposed for reconstruction. This was removed in 1994 during construction and not replaced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Replaced Otsego County Monument in corner from Wakenhut's T & P Pole NE, 1/2" iron rod east 33.0 (Cert. of Survey, L. 416, P.359) and measurements north & south to G-11 & G-13, respectively, proportioned to previous measurements on file in my office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument in corner is accepted as a careful and faithful reestablishment of the position of the original corner. Spike in P. Pole N 60°E 32.01', 1/2" iron rod N 85°E 33.00', spk P. Pole S 15°E 87.13', spk P. Pole N 40°W 37.97'.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Pool  
 Group, pursuant to Act 345, PA 1990.  
 11/2/95 Donald [Signature]  
 /Date V. Chairman



Signed by Carl I. Robinson Date October 10, 1995  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390