

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 136

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

95 DEC -6 PM 1:30

EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 3 W	H-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl I. Robinson, in a field survey on October 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:


CSR 3/98: G.F. DeLaMater, undated: Concrete Monument placed by guess on our north & south (±) line by survey party working on Sanitarium Survey, 2609' north of ½ (7). (Ed. State crew used incorrect procedure).
 LCRC 2/170: C.I. Robinson, 1980: Set Otsego County Monument at the intersection of ½ lines-spk P.Pole N 25°E 90.61', steel Fence Post S 60°E 35.19', ¾" iron pipe in Concrete Monument S 3°E 1.52', spk Corner Fence Post S 87°W 34.57'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument 3'± west of centerline graded road, broken Concrete Monument south 1½'±, P.Pole NE, and Fe.Post SE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument 6" deep and 3'± west of centerline graded road, this position was not established by original government surveyors, this monument is accepted as the best available evidence of the position of the corner-spk P.Pole N 23°E 90.42', 2½" Steel Gate Post N 59°E 40.15', ½" capped Iron Rod N 88°W 32.50', 1"x34" Orange Top Pipe N 48°W 29.60'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

11/27/95 Donald E. Seaman
 Date J. Chairman

Signed by Carl I. Robinson
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

Date November 21, 1995