

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 OTSEGO COUNTY
 ALSO Act 345, PA 1990 MICHIGAN

For corners in

OTSEGO (County)	Located In:	Corner Code #/
1. Public Land Survey	T 31 N R 3 W	H-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

95 DEC -6 PM 1:30

EVELYN H. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Carl I. Robinson, in a field survey on October 27, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
 GLO 2/286: Austin Burt, 1850: Set Qt. Sec. Post-Sugar 30" S 37°W 12 lks (7.9'), Beech 8" N 40°E 15 lks (9.9').
 CSR 2/322: G.F. DeLaMater, 1929: Found old post in center of road, 1/2"x30" bar in corner, fence in line east-pointed Stone N 42°E 50.0', Elm 12" S 10°W 62.1'. 1936 1/2" pipe in corner-Concrete Monument N 45°E 48.0'.
 LCRC 1/165: W.W. Wakenhut, 1972: Found 3/4" Iron-spk P.Pole East 38.78', spk W. Root 24" Maple S 40°W 29.12', Subdivision Monument S 45°W 29.12'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument 16" deep, 5' north & 6' west of intersection of centerlines of bituminous pavements north-south (Hayes Rd.) and west (McLouth Rd.), fence line to east and DeLaMater's Concrete filled Pipe Monument northeast.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument at surface over Otsego County Monument, 5' north & 6' west of intersection of bituminous pavements north-south (Hayes Rd.) and west (McLouth Rd.), accepted as a careful and faithful perpetuation of the position of the original corner-Concrete filled Pipe Monument N 45°E 47.80', 1/2" Capped (#8897) Iron Rod East 33.04', Concrete Monument (subdivision) S 46°W 46.57', Concrete Monument (with 3/4" Iron Pipe extended with 3/8" Iron Pipe) N 43°W 46.89'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

11/27/95 Date [Signature] V. Chairman

November 21, 1995

Signed by [Signature]
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390