

OTSEGO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
95 DEC -6 PM 1:31  
EVAN H. PRATT  
CLERK / REGISTER OF DEEDS

For corners in

| OTSEGO<br>(County)                    | Located In:             | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey                 | T 31 N R 3 W            | I-10          |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims _____               |                         |               |

Register of Deeds Stamp & File Number

I, Carl I. Robinson, in a field survey on November 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G  | H  | I  | J | K | L |
|----|----|----|----|----|----|----|----|----|----|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |    |    |    |   |   |   |
| 3  |    |    |    |    |    |    |    |    |    |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |    |    |    |   |   |   |
| 5  |    |    |    |    |    |    |    |    |    |   |   |   |
| 6  | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |
| 7  |    |    |    |    |    |    |    |    |    |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |    |    |    |   |   |   |
| 9  |    |    |    |    |    |    |    |    |    |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |    |    |    |   |   |   |
| 11 |    |    |    |    |    |    |    |    |    |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |    |    |    |   |   |   |
| 13 |    |    |    |    |    |    |    |    |    |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 2/280: Austin Burt, 1850: Set Qr. Section Post-Hemlock 20" S 88°E 26 lks (17.2'), Sugar 30" S 46°W 17 lks (11.2')  
 CSR 2/269: G.F. DeLaMater, 19??: Found roots of both Gov't D's & P, 3/4"x18" Iron- Sugar 8" N 55°E 16.9', Hemlock 10" N 37°W 38.7'.  
 LCRC 2/170: C.I. Robinson, 1980: Found 5/8" iron at intersection of very old E-W & N-S fence lines and DeLaMater's blazed Maple & Hemlock, Set Otsego County Monument-spk 10" Maple N 55°E 17.06', spk 7" Maple S 10°E 14.47', spk in root 18" Maple West 2.13', spk 10" Hemlock N 37°W 39.24'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Otsego County Monument in very old B.Wire fence on hillside west of swamp, DeLaMater's Maple (dead) and Hemlock (stump), Robinson's spikes in these and in root of 18" Maple (stump).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Otsego County Monument in very old B.Wire fence N & S on hillside west of swamp-spk 5" Maple (w/B.Wire) N 10°W 7.49', spk 18" Beech S 15°W 28.24', spk in root 18" Maple (stump) West 2.20', spk 28" Beech N 44°W 43.00'.  
 Accepted as a careful and faithful perpetuation of the position of the original corner.



OTSEGO COUNTY REMONUMENTATION  
 Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
 11/27/95 [Signature]  
 Date V. Chairman

Signed by [Signature] Date November 22, 1995  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390