

MAY 28 1997

COMMISSION

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

For corners in

<u>OTSEGO</u> (County)	Located In: Elmira Twp.	Corner Code # <u>C-11</u>
1. Public Land Survey	T <u>31N</u> R <u>4W</u>	<u>C-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

OTSEGO COUNTY MICHIGAN RECEIVED FOR RECORD

95 DEC 30 PM 2: 17

EVELYN M. PRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl I. Robinson, in a field survey on November 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GLD 2/412: Austin Burt, 1850: Set Post-Sugar 30" S 23°E 15 lks (9.9'), Beech 6" N 74°W 32 lks (13.9').
- CSR 2/194: G.F. DeLaMater, 1919: Established piece of plow casting in corner-Elm 6" S 27°50'E 109½ lks (72.3'), Sugar 4" N 48°W 110½ lks (72.8').
- CSR 2/198: G.F. DeLaMater, 1938: Gas Pipe in Corner-Plow Beam N 45°E 46.7', Elm 2" S 45°E 46.3'.
- CSR 3/120: G.F. DeLaMater, 1938: 1" iron in corner O.K.-Concrete Monument S 45°E 48.0', Concrete Monument S 45°W 64.0'.
- LCRC 2/69: G.R. McKelvey, 1977: Found G.F.D. Gas Pipe-PK in P.Pole N 50°E 37.75', PK in P.Pole S 45°E 48.87', PK in Wood Post S 60°W 69.89', PK in P.Pole N 55°W 73.91'.
- Misc.: C.I. Robinson, 1985: Set Otsego County Monument at Gas Pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument, DeLaMater's Concrete Monument southwest, and McKelvey's P.Pole southeast & Wood Post Southwest.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument: 2'± east of east edge of metal; and is accepted as a careful and faithful reestablishment of the position of the original corner-spk 11" Aspen N39°E 64.76', PK P.Pole S 42°E 48.87', Concrete Monument S 45°E 64.03', spk 4"x4" Post S 67°W 70.03', spk 10" Elm N 71°W 86.75'.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

11/26/96 Date Donald E. Sorenson V. Chairman



Signed by Carl I. Robinson
Surveyor's Michigan License No. 16390

Date November 25, 1996