

SURVEY & REMONUMENTATION

MAY 28 1997

For corners in **COMMISSION**

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
96 DEC 30 PM 2:17
EVELYN H. PRATT
CLERK / REGISTER OF DEEDS

OTSEGO (County)	Located in: Elmira Twp.	Corner Code #
1. Public Land Survey	T 31 N R 4 W	C-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl I. Robinson, in a field survey on November 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:**
 GLD 2/413: Austin Burt, 1850: Set Qr. Section Post-Sugar 10" West 30 lks (19.8'), Beech 8" N 80°E 28 lks (18.5').
 CSR 1/65: A.W. Bates, 1891: Found bearing tree & Post-Beech N 48°E 36 lks (23.8'), Sugar 20" S 67°E 60 3/4 (40.1').
 CSR 2/194: G.F. DeLaMater, 1919: Found Sugar stump corresponding to B, Blacksmith Tongs in corner-Beech 6" 106 1/2 lks (70.4'), Maple shade 4" S 89°08'W 147 3/4 lks (97.5').
 CSR 2/198: G.F. DeLaMater, 1938: 1 1/2" T Rail in corner-Sugar 8" S 36°E 77.8'.
 LCRC 2/119: G.R. McKelvey, 1978: Found R.R. Rail-spk P.Pole N 15°E 89.43', spk 5" Maple East 47.84', spk 20" Tw. Maple S 80°W 88.80', 1/2" Iron Rod N 80°W 13.19'.
 Misc.: C.I. Robinson, 1985: Set Otsego County Monument over RR Rail.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
 Found Otsego County Monument, DeLaMater's Maple West, McKelvey's P.Pole NE & Tw. Maple SW.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
 Otsego County Monument 1± W. of pavement centerline, accepted as a careful and faithful perpetuation of the position of the original corner-spk P.Pole N 21°E 89.35', spk 6"x8" Corner Fence Post East 31.95', spk Tw. 16" & 30" Maple S 79°W 88.80', spk 22" Maple S 85°W 98.00'.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 11/26/96 J.E. Sorensen
 Date V. Chairman



Signed by Carl I. Robinson
 Surveyor's Michigan License No. 16390, PE & PS, Otsego County Surveyor

Date November 25, 1996