

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

OTSEGO COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 ALSO Act 345, PA 1990

For corners in

Table with columns: OTSEGO (County), Located In: Elmira Twp., Corner Code #, and survey details for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

OTSEGO COUNTY MICHIGAN RECEIVED FOR RECORD 96 DEC 30 PM 2:17 EVELYN M. PRATT CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Carl I. Robinson, in a field survey on November 25, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numerical values for survey points.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of survey descriptions including GLO 2/438, CSR 1/54 & 1/55, CSR 1/96 & 1/97, CSR 3/16, LCRC 1/213, and Misc.: C.I. Robinson, 1985.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument, DeLaMater's Monument NE & Sugar SE, and McKelvey's P.Poles NE & NW.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument 1± E. of centerline of bit. pavement, accepted as a careful and faithful perpetuation of the position of the original corner-Concrete Monument N 45°E 46.65', hook in face P.Pole base N 46°E 45.24', spk 36" Maple (face) S 45°E 53.35', hook S. side P.Pole N 50°W 51.41'.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

11/26/96 Date Y. Chairman



Signed by Carl I. Robinson, PE & PS, Otsego County Surveyor Surveyor's Michigan License No. 16390

Date November 26, 1996