

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

OTSEGO COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 ALSO Act 345, PA 1990

For corners in

OTSEGO (County)	Located In: Elmira Twp.	Corner Code #
1. Public Land Survey	T 31 N R 4 W	E-6
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

OTSEGO COUNTY MICHIGAN RECEIVED FOR RECORD

96 DEC 30 PM 2:17

EVELYN H. PRATT CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl I. Robinson, in a field survey on November 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
GLO 2/438: Austin Burt, 1850: Set Qr. Section Post-Sugar 30" S 55°E 43 lks (28.4'), Sugar 30" N 51°W 35 lks (23.1').
CSR 1/54 & 1/55: A.W. Bates, 1891: Found Gov't B & P-Hemlock 20" S 63½°E 66½ lks (43.9'), Sugar 18" S 85½°W 76 lks(50.2)
CSR 3/58: G.F. DeLaMater, 1934: Found Bates P, set ½"x36" bar in corner-Concrete Monument East 33.0', Elm 10" West 37.7'.
CS 554/72: J.L. Schwandt, 1994: Found ½" Bar 1.2' west of Road Q & Concrete Monument East 33.08', MBT Box S 35°W 91.95', P.Pole S 50°W 67.12'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found ½" Iron Rod 15" deep, DeLaMater's Monument East, Schwandt's "MBT" Box & P.Pole SW.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Otsego County Monument over ½" Iron Rod 1'± W. of centerline of bit pavement, accepted as a careful and faithful perpetuation of the position of the original corner-Concrete Monument East 33.35', ½"x36" ½" Iron Pipe S 31°E 64.65', nail Cedar Post at Telephone Terminal S 33°W 92.36', nail P.Pole S 47°W 67.16'.

OTSEGO COUNTY REMONUMENTATION
Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
Date 11/26/96
V. Chairman



Signed by [Signature]
Carl I. Robinson, PE & PS, Otsego County Surveyor
Surveyor's Michigan License No. 16390

Date November 26, 1996