

OTSEGO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

For corners in

OTSEGO (County)  
 Located in: Elmira Township  
 Corner Code # E-7

1. Public Land Survey T<sup>31</sup>N R<sup>4</sup>W  
 T R  
 T R  
 T R

2. Property Controlling in Section S T R  
 S T R

3. Miscellaneous Property in Sec. S T R  
 S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

OTSEGO COUNTY MICHIGAN  
 RECEIVED FOR RECORD  
 96 DEC 30 PM 2:17  
 EVELYN H. PRATT  
 CLERK / REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl I. Robinson, in a field survey on December 4, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 2/439: Austin Burt, 1850: Post-Sugar 14" N 43°E 17 lks (11.2'), Sugar 16" S 10°W 33 lks (21.8').  
 CSR 1/25: W.F. Sanborn, 1888: Sugar 8" S 45°W 46 lks (30.4'), Sugar 20" N 77°W 33½ lks (22.1').  
 CSR 1/54 & 55: A.W. Bates, 1891: Found Road Survey B & P-Elm 36" S 20°E 166 2/3 lks (110.0'), Elm 20" N 29°W 51½ lks (33.3).  
 CSR 2/410: G.F. DeLaMater, 1934: Found Corner, placed ¼"x30"-Sugar 10" N 59°E 52.2', Concrete Monument S 45°E 46.7'.  
 LCRC 1/175: J.L. Wilcox, 1972: Set RR Spike by witness from DeLaMater 1934 survey and concurrent distance from N ¼ corner-Top Center Concrete Project Marker N 45°E 40.00', Concrete Monument S 45°E 46.7', T.Pole N 65°W 98.17'.  
 Misc.: C.I. Robinson, 1985: Set Otsego County Monument at RR Spike-Witnesses O.K. (Confirmed by Schwandt survey 1994).  
 Survey 603/791: J.L. Schwandt, 1996: Found Otsego County Monument-P.Pole N 45°E 40.58', Concrete Monument S 45°E 46.7', 15" R.Pine S 39°W 58.72', Fe.Post S 49°W 54.75'.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Otsego County Monument, DeLaMater's Sugar & Monument, and all of Wilcox's & Schwandt's Witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Otsego County Monument 1' west of centerline on bituminous pavement and is accepted as a careful and faithful reestablishment of the position of the original corner-tag 26466 Base of T.Pole N 45°E 40.58', nail 27" Maple N 59°E 52.00', Concrete Monument S 45°E 46.76', tag 26466 P.Pole S 20°E 90.50', tag 3920 Base of T.Pole S 49°W 54.64', tag 3920 Base of T.Pole N 57°W 98.17'.



OTSEGO COUNTY REMONUMENTATION  
 Approved by the County Surveyor Peer Group, pursuant to Act 345, PA 1990.  
 12/13/96 Donald E. Sagan  
 Date V. Chairman

Signed by Carl I. Robinson  
 Surveyor's Michigan License No. 16390  
 PE & PS, Otsego County Surveyor

Date December 11, 1996

LIBER 0004 PAGE 204