

**SURVEY &
REMONUMENTATION**

MAY 28 1997

COMMISSION

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990**

For corners in

OTSEGO <small>(County)</small>	Located In: Elmira Township	Corner Code #
1. Public Land Survey	T <u>31</u> N R <u>4</u> W	I-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD

96 DEC 30 PM 2:19

EVELYN H. PRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl I. Robinson, in a field survey on December 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 2/402: Austin Burt, 1850: Set Post-Sugar 10" S 48°E 47 lks (31.0'), Lynn 14" N 54°W 15 lks (9.9').
- CSR 1/12: J.M. Sanborn, 1881: Elm 10" N 56°E 80 lks (52.8'), Sugar 10" S 48°E 47 lks (31.0').
- CSR 1/18: J.M. Sanborn, 1883: Maple 24" S 68°E 30½ lks (20.1'), Sugar 10" S 47°E 47 lks (31.0'). CSR1/28: 1884:(same).
- CSR 2/234: G.F. DeLaMater, undated: Found P at road intersection: 1932: Found Large Casting in corner-Concrete Monument N 45°E 46.7', Concrete Monument S 45°W 46.7'.
- LCRC 1/213: G.R. McKelvey, 1973: Set ½" Iron Rod from reference Monuments-Concrete Monument N 45°E 47.07', Concrete Monument S 45°W 47.07', T.Pole N 45°W 53.19'.
- LCRC 2/327: C.I. Robinson, 1985: Found McKelvey's Iron Rod & all References-Concrete Monument N 45°E 47.07', Concrete Monument S 45°W 47.07', Tag #19001 T.Pole N 45 W 53.19'. Set Otsego County Monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument in Mon.Box & DeLaMater's Monument SW (Monument NE removed during road construction).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument at intersection of centerlines of roads, and is accepted as a careful and faithful perpetuation of the position of the original corner-Form Nail 10"± R.Pine S 45°E 84.60', Concrete Monument S 47°W 47.07', Cut Nail P.Pole N 53°W 53.70', MDOT Horizontal Control Monument (#69203 "1991") N 36°W 47.57'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Date Dec 13 1996 Dave E. Sagan
Y, Chairman

Signed by Carl I. Robinson
Surveyor's Michigan License No. 16390

December 12, 1996