

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 058

OTSEGO (County)	Located In:	Corner Code --#
1. Public Land Survey	T 31 N R 2 W	L-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

94 DEC 29 PM 1:34

EVLYNN H. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl I. Robinson, in a field survey on December 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO 2/164: A. Burt, 1850: Set Post-Hemlock 36" N 28°E 24 lks (15.8'), Beech 12" S 12°E 29 lks (19.1').
 CSR 2/440: G.F. DeLaMater, 1931: ½"x30" bar established midway on line-Pointed Stone N 39°E 41.8', Pointed Stone S 39°W 41.4'. (Note: OCRC set Mon. Box per 1966 Construction Plans).
 LCRC 2/161: J.L. Schwandt, 1980: Found ½" bar in Mon. Box-P. Pole N 67°W 102.75', Cor. Fe. Post N 10°E 34.22', Cor. Fe. Post South 33.30', Fe. Post N 38°E 43.92'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found ½" Iron Rod in monument box on centerline of pavement and fence line to south, 7.6'± west of fence to north, one OCRC 1966 witness, and all 1980 witnesses.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 ½" Iron Rod in Monument box on centerline of pavement and fence line to south, 7.6'± west of fence to north, and is accepted as a careful and faithful reestablishment of the position of the original corner-Tag Fence Corner Post N 18°E 34.65', Tag Fence Post N 44°E 43.79', nail Fence Corner Post S 5°W 33.40', tag P. Pole N 67°W 102.75'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

12/22/94 Date V. Chalmers

Signed by Carl I. Robinson
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

December 21, 1994