

SURVEY & REMONUMENTATION

APR 25 1995

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

LIBER 0001, PAGE 59

For corners in
COMMISSION
OTSEGO
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 31 N R 2 W | M-4 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 29 PM 1:34
LYLE W. PRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Carl I. Robinson, in a field survey on December 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 2/10: J. Mullett, 1840: Post-Pine 14" S 47°W 06 lks (4.0'), Tamarack 10" N 47 E 03 lks (2.0').
 CSR 3/124: G.F. DeLaMater, 1938: Found one Gov't B & P, ½"x36" iron in corner- W. Pine stump 14" N 34°E 42.3', W. Pine stump 18" N 47½°W 68.1'. Conservation Department, 1951: 1" Pipe w/4" brass cap-Cedar 8" N 78°E 53 lks (35.0'), R. Pine stump 18" N 55°W 9 lks (5.9').
 LCRC 2/143: G.R. McKelvey, 1979: Found DNR monument & prio CSR witnesses-½" Iron Rod S 85°E 19.18', spk 7" Spruce S 23°W 22.20', spk Fe. Post North 24.33', spk Fe. Post West 16.74'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found DNR Monument 0.5' northeast of fence corner post, both DeLaMater's W. Pine stumps, Conservation Department's Cedar, McKelvey's fence post West & ½" iron rod East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monument 0.5' northeast of fence corner post is accepted as a careful and faithful perpetuation of the position of the original corner, nail 14" R. Pine N 46°E 74.90', nail 12" Cedar N 78°E 35.68', nail 9" Cedar S 39°E 49.95', nail 8" Cedar N 24°W 57.38'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

12/22/94
Date

J. Chairman
Chairman

Signed by Carl I. Robinson
Carl I. Robinson, PE & PS, Otsego County Surveyor
Surveyor's Michigan License No. 16390

Date December 20, 1994