

MAR 17 2000

OTSEGO COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Also Act 345, PA 1990

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD

00 JAN 10 AM 10:10

EVELLYN M. PRATT
CLERK / REGISTER OF DEEDS

For corners in

Otsego	Located In:	Corner Code #
(County)	Corwith Township	
1. Public Land Survey	T <u>32N</u> R <u>2W</u>	<u>I-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, James L. Schwandt, in a field survey on Jan. 19, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9									●				
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|--|---|
| <p>1. I-9, T32N-R2W
G.L.O. John Mullett
June 21, 1850
Set Maple post
Y. Pine, 15", N52°W, 18 links (11.88')
Aspen 15", S26°E, 9 links (5.94')</p> | <p>2. Delamater, 1931
1/2" X 30" bar in corner
Found one Gov't B, plainly marked
Y. Pine 10", S66°W, 151.0'
Y. Pine, 5", N66°E, 102.9'</p> | <p>3. Carl I. Robinson, 1980
Fnd 1/2" iron in corner
Set Otsego County Mon.
Set spk 12" Pine, N66°E, 103.71'
Set spk 7" Aspen, N05°E, 19.60'
Set spk 4" W. Pine, N35°E, 28.79'
Set spk, fence post, South 5.95'</p> |
|---|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument
Fence post, South, +/- 6'



C. Description of monument for corner and accessories established to perpetuate locating the position of the

Otsego County Monument in corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 10" Twin W. Pine, S40°E, 10.34
- 10" R. Pine, N22°W, 42.71'
- 10" W. Pine, N88°W, 46.32'
- 6" W. Pine, S05°W, 31.04'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer
Group, pursuant to Act 345, PA 1990.

Dec. 29, 1999
Date

[Signature]
Chairman

Signed by James L. Schwandt
Surveyor's Michigan License No. 26466

Date 12-28-99