

MAR 17 2000

OTSEGO COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Also Act 345, PA 1990

OTSEGO COUNTY MICHIGAN
RECEIVED FOR RECORD

00 JAN 10 AM 10:10

LYVELYN M. PRATT
CLERK / REGISTER OF DEEDS

For corners in

Otsego (County)	Located In: Corwith Township	Corner Code #
1. Public Land Survey	T <u>32N</u> R <u>2W</u>	<u>I-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James L. Schwandt, in a field survey on Jan. 19, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10, T32N-R3W	County Survey Records (3-458)	C. Robinson, 12-3-79
G.L.O. John Mullett, June 21, 1850	S. Thorsen R.S. #5788	L.C.R.C. (2-155)
Set Hemlock Qrt Sec Post	Sept. 25, 1959	Found 1/2" iron pipe, replaced w/O.C.M.
W. Pine, 40", N31°E, 35 links (23.10')	Placed 1/2" bar M.P.O.L.	Set spike 10" R. Pine, N22°E, 28.19'
Beech, 8", S39°W, 20 Links (13.20')	R. Pine 6" S38°E, 23.0'	Set spike 7" R. Pine, S63°W, 23.18'
	R. Pine 8", S63°W, 22.8'	Set spike 9" R. Pine, S38°E, 23.47'
	R. Pine 6", N22°E, 27.9'	Set spike 6" Aspen, N70°E, 21.15'

Recorded survey (371-470)
George Avendt Jr. 11-10-85
Found O.C.M.
Found spk in 12" R. Pine N22°E, 28.15'
Found spk in 10" R. Pine, S63°W, 23.26'
Found spk in 8" R. Pine, S38°E, 23.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Otsego County Mon, Set by Carl Robinson, 1979
10" R. Pine, N22°E, 28.19'
9" R. Pine, S38°E, 23.47'
7" R. Pine, S63°W, 23.18'
6" Aspen, N70°E, 21.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Mon. in corner is accepted as a careful and faithful reestablishment of the position of the original corner.
10" R. Pine, N22°E, 28.19'
9" R. Pine, S38°E, 23.47'
7" R. Pine, S63°W, 23.18'
6" Aspen, N70°E, 21.15'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer
Group, pursuant to Act 345, PA 1990

Dec. 29, 1999
Date

[Signature]
Chairman

Signed by James L. Schwandt

Date 12-28-99

Surveyor's Michigan License No. 26466

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197
REVISED MAY 14, 197
REVISED JAN., 198
REVISED OCT., 199

