

MAR 17 2000

SECTION

OTSEGO COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Also Act 345, PA 1990

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

00 JAN 10 AM 10:10

EVELYN H. PRATT  
CLERK / REGISTER OF DEEDS

For corners in

Otsego	Located In:	Corner Code #
(County)	Corwith Township	
1. Public Land Survey	T <u>32N</u> R <u>2W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, James L. Schwandt, in a field survey on Jan. 19, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11 T32N-R2W G.L.O. John Mullett, June 22, 1850 Set Hemlock 1/4 Sec Post W. Pine 24" N24°W, 45 links (29.70')	Delamater 1938 Dug up old post 1/2" X 36" iron Conc Mon S45°W, 48.00' Pine 8" N64°W, 49.30' Pine Stp. 20" S24°W, 52.00'	James L. Schwandt #26466 1982, 1987, 1988 Fnd 1/2" bar 14" R. Pine N30°W, 48.70' 14" R. Pine N30°E, 12.57' Fence corner S40°E, 55.99' Conc Mon S45°W, 48.10'
R.C. Dunn #12020, 1983 Fnd 1/2" iron bar 14" R. Pine N30°W, 48.70' 14" R. Pine, N30°E, 12.57' Fence corner S40°E, 55.99' Conc. Mon S45°W, 48.10'	James L. Schwandt #26466 1996 Fnd 1/2" bar 18" R. Pine N30°E, 12.57' 12" R. Pine S38°E, 40.49' Fence Post S2°W, 32.55' 15" R. Pine N30°W, 48.70'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar  
 18" R. Pine N30°E, 12.57'  
 15" R. Pine N30°W, 48.70'  
 12" R. Pine S38°E, 40.49'  
 Fence Post S2°W, 32.55'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990

Dec. 29, 1999  
Date

*[Signature]*  
Chairman



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set O.C.M. Monument in corner and is accepted as a careful and faithful perpetuation of the position of the original corner.  
 18" R. Pine N30°E, 12.57'  
 12" R. Pine S38°E, 40.49'  
 Fence post S2°W, 32.55'  
 15" R. Pine N30°W, 48.70'

Signed by James L. Schwandt  
 Surveyor's Michigan License No. 26466

Date 12-28-99