

MAR 17 2000

OTSEGO COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Also Act 345, PA 1990

For corners in

Form with fields: Otsego (County), Located In: Corwith Township, Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

OTSEGO COUNTY MICHIGAN RECEIVED FOR RECORD 00 JAN 10 1999 MICHIGAN RECEIVED FOR RECORD EVELYN H. PRATT CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a dot in cell J9.

I, James L. Schwandt, in a field survey on Jan. 19, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. K-9, T32N-R2W G.L.O. John Mullett June 21, 1850 Set Post W. Pine 16", N26°E, 39 links (25.74') W. Pine 15", S52°W, 20 links (13.20')
2. County Survey Records (4-466) Unknown Gas pipe in concrete No witnesses given
3. L.C.R.C. (2-153) C. Robinson, 11-26-79 Found gas pipe (not in concrete); replaced corner w/ O.C.M. Set spk, in 16" Twin Oak, N80°W, 23.70' Spk in 15" Oak, S68°E, 33.76' Spk in 10" Oak, S10°E, 12.68' Spk in 7" Multi-Maple, N35°E, 49.47'
4. James L. Schwandt Found Otsego County Mon, 1987 1990 10" Oak, S10°E, 12.68' 16" Twin Oak, N80°W, 23.70' 15" Oak, S68°E, 33.76' 8" Tri Maple, N35°E, 49.47'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found Otsego County Monument (Carl Robinson, 1979) Found Maple Stump, N35°E, 49.47' Found 15" Oak Stump, S68°E, 33.76' Found 10" Oak Stump, S10°E, 12.68' Found 16" Twin Oak, N80°W, 23.70'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument at intersection of fence lines to East and South, and is accepted as the best available evidence of the position of the original corner. P.P., S49°E, 28.41' 6" Maple, S68°W, 5.22' 16" Twin Oak, N80°W, 23.70' P.P., N06°W, 82.45'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Dec. 29, 1999 Date Chairman

Signed by James L. Schwandt Date 12-28-99 Surveyor's Michigan License No. 26466

