

OTSEGO COUNTY REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO ACT 345, PA 1990

For corners in

<u>Otsego</u> (County)	Located In: <b>Corwith Township</b>	Corner Code # <b>C-3</b>
1. Public Land Survey	T <u>32N</u> R <u>3W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
96 DEC 30 PM 2:16  
EVELYN M. PRATT  
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **James L. Schwandt**, in a field survey on **Nov. 21, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3		●										
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- |   |  |   |   |
|---|--|---|---|
| C-3 T32N-R3W<br>G.L.O. William Burt, 1850 (P374)<br>Set Sugar Post<br>Sugar 12" N39°E, 18 Links (11.88')<br>Sugar 10" S22°W, 13 Links (8.58') | CSR (2-306)<br>G.F. Delamater, 1926 & 1932<br>Fnd Hoffman's Cor w/Iron<br>NE Cor School S45°W, 98.5'<br>Pointed Stone N45°E, 37.00'<br>Sugar 24" S87°W, 72.0'<br>C.M. S45°E, 48.0'<br>1/2" x 30" Bar @ Cor | LCRC (1-289)<br>W.W. Wakenhut, 1973<br>Fnd Large Spike<br>Dip Needle Indicates and Iron Below<br>C.M. S45°E, 48.0'<br>Spk 8" Maple N50°W, 84.04'<br>Spk 15" Maple N20°E, 35.12' | Unrecorded Survey<br>J. L. Schwandt, 1979<br>Fnd Spike as per W.W.W. Witnesses<br>Fnd C.M. S45°E, 47.97'<br>Fnd 8" Maple N50°W, 84.04'<br>Fnd 15" Maple N20°E, 35.12' |
|---|--|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- Fnd 3/8" Iron Bar under PK Nail
- Fnd Broken C.M. S45°E, 47.97'
- Fnd Nail in 14" Maple N50°W, 84.04'
- Fnd Nail in 24" Maple Stump N20°E, 35.12'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set O.C.M. over fnd iron, and is accepted as a careful and faithful perpetuation of the position of the original corner.
- Set Nail & Tag #41099 in P.P. N47°E, 55.79'
- Set Nail & Tag #41099 in P.P. S46°E, 56.25'
- Set Nail & Tag #41099 in P.P. S46°W, 51.95'
- Fnd Nail in 14" Maple N50°W, 84.04'
- Fnd Nail in 24" Maple Stump N20°E, 35.12'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990  
 Date Dec. 13, 1996 Chairman [Signature]



Signed by James L. Schwandt  
 Surveyor's Michigan License No. 26466

Date 12-13-96