

MAR 17 2000

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD

00 JAN 10 AM 10:12

EVELYN M. PRATT
CLERK / REGISTER OF DEEDS

For corners in

ALSO Act 345, PA 1990

Located In:	Corner Code #
<u>Otsego</u> (County)	<u>G-11</u>
1. Public Land Survey	T <u>32N</u> R <u>3 W</u>
	T <u> </u> R <u> </u>
	T <u> </u> R <u> </u>
	T <u> </u> R <u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>
	S <u> </u> T <u> </u> R <u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>
	S <u> </u> T <u> </u> R <u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl I. Robinson, in a field survey on December 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 2/347: William Burt, 1850: Set Beech Post-Beech 12" N 24°E 21 lks (13.9'), Beech 15' S 37°W 39 lks (25.7').
- CSR 1/11 & 1/21: J.W. Sanborn, 1881 & 1883: Hemlock 18" N 29½°E 1.04 ch. (68.6'), Hemlock 24" N 80°W 51 lks (33.7').
- CSR 2/494: G.F. DeLaMater, 1932: Found sleigh shoe in corner, set ½" Gas Pipe-Sugar 6" S 63°E 96.1', Concrete Monument S 44°E 48.0', Elm 12" S 27°W 65.2', Sugar 24" N 44°W 37.3'.
- CSR 3/452: Michigan Highway Dept, 1959: RR Iron Bolt Spike in Corner, P.Pole N 60°E 63.49', T.Pole S 30°E 57.74', P.Pole N 25°W 64.51'.
- LCRC 1/101: W.W. Wakenhut, 1972: Found 3/4" Bar over 5/8" Bolt of Record-spk P.Pole N 65°E 63.48', spk in N.E.S. Root 30" Maple S 85°W 103.36', spk in S.S. Root 42" Maple N 40°W 72.95', spk P.Pole N 25°W 64.50' (MSHD Tag).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4"x8" Iron Rod over 5/8" Bolt in remains of very old wood stake, Highway Department's 42" Maple & P.Pole NW, also fits GLO distances west to F-11 and south to G-12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2½"x10" Otsego County Monument over 5/8" Bolt in remnants of old wood stake, G.Pole N 48°E 48.45', spk P.Pole S 46°E 32.93', spk S.S. Root 42" Maple N 47°W 72.91', spk in MSHD Tag P.Pole N 27°W 64.50', accepted as a careful and faithful perpetuation of the position of the original corner.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 12/29/99 Date J.E. Sagan Chairman

Signed by Carl I. Robinson
 Surveyor's Michigan License No. 16390

Date December 17, 1999