

SURVEY & REMONUMENTATION

FEB 27 1998

Ottawa County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Ottawa <small>(County)</small>	Located In:	Corner Code ##	
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>A-5</u>	
	T _____ R _____	<u>Jamestown Twp.</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECORDED

97 DEC -8 AM 11:29

[Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on Nov. 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5 LCRC Liber 1, Page 685 (Oct. 9, 1972) "T" iron set in ϕ X roads N&S&E and 264.0' E of S 1/4 cor., Sec. 12-5-14, and on line of SE cor. and S 1/4 cor Sec. 12 MBT pole N50°E 48.62' MBT pole N30°W 73.75' CP pole S40°W 55.28'	LCRC Liber 4, Page 331 (Sept. 24, 1982) Set Cast Iron Mon. Tele. Pole NW 73.64' Power Pole SW 52.95' Guy Pole SSE 62.51' Tele. Pole NE 49.48'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found Cast Iron Monument
 No witnesses found as previously recorded.
 Ottawa County Mon. (M-5, Zeeland Twp.) N4°E 44.16'

Re-witnessed C.I.M. and replaced with Ottawa County Cap on 24" X 3/4" Steel Bar in Mon. Box upon completion of road construction.

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12-1-97

[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 Standard Ottawa Co. Cap on 24" X 3/4" Steel Bar in Mon. Box
 Nail & Tag in E end 24" CMP N24°E 88.51'
 Nail & Tag in E end 18" CMP S45°E 41.48'
 NE cor. hse. fndn. N20°W 251.16'
 SW cor. conc. porch N32°W 226.87'
 Nail & Tag in E side PP S35°W 45.21'
 Nail & tag in E side PP N5°W 206.60'
 O.C. Mon (M-5, Zeeland Twp.) N4°E 44.24'
 On ϕ N-S BT road
 On ϕ BT road to East extended



Signed by Rodney D. Unema Date Dec. 1, 1997
 Surveyor's Michigan License No. 33987