

**SURVEY &
REMONUMENTATION**

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>OTTAWA</u> (County)	Located In: Jamestown Township	Corner Code #: C-5
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 15 PM 2:11

Rodney D. Unema
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Rodney D. Unema, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-5 Corner common to Sections 7, 8, 17 and 18
Dec., 1831 original gov't LCRC Liber 2, Page 55
corner set by Sylvester Sibley (Sept., 1974)
Found "T" iron
7" Beech at corner SW cor porch fndn ENE 86.48'
NW cor Hse # 3188 fndn
SE 95.16'
Spike in W'ly sde 12" Maple
NNW 88.24'
PK in E'ly sde P. Pole SSE 51.94'

LCRC Liber 5, Page 259
(August, 1986)
Set C.I.M.
NW cor hse # 3188 fndn
ENE 86.48'
PK in P. Pole SSW 51.94'
SW cor hse Fndn NE 79.35'
PK in P. Pole NNW 91.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 Found 4" diameter C.I.M. in Mon. Box at ϕ "X" of Riley and 40th
Found PK nail in E sde P. Pole S26°W 51.94'
Found PK nail in E sde P. Pole N08°W 91.07'
SW cor of brick porch fndn N37°E 71.12'
NW cor block fndn house # 3188 S41°E 95.20'

Accepted as a careful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 Corner common to Sections 7, 8, 17 and 18
4" Cast iron monument in monument box at intersection of Riley and 40th
Set nail & OC tag in E sde P. Pole S26°W 51.95'
Set nail & OC tag in E sde P. Pole N08°W 91.06'
SW cor of brick porch fndn N37°E 71.12'
NW cor block fndn Hse # 3188 S41°E 95.20'



Signed by Rodney D. Unema Date October 20, 1995
Surveyor's Michigan License No. 33987