

**SURVEY &
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

RECORDED

95 NOV 15 PM 2:11

Rodney D. Unema
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

OTTAWA (County)	Located In:	Corner Code #
	Jamestown Township	
1. Public Land Survey	T 5N R 13W	C-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Rodney D. Unema, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7 Corner common to Sections 17, 18, 19 and 20	LCRC Liber 3, Page 128	LCRC Liber 5, Page 183
Dec., 1831, original corner	(Nov., 1976)	(Dec., 1984)
set by Sylvester Sibley	Iron pipe	Set cast iron monument
Set post	NE cor gas Station	Power pole
12" Beech S22°E 19 links	SW 103.77'	NNE 61.59'
6" Beech N89°W 7 links	NW cor hse	Power pole
	SE 86.15'	WSW 76.62'
		NE gas station cor
		SW 103.77'
		NW hse corner
		SE 86.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found 3" cast iron monument in monument box (6" below top of box)
Monument is 3' West of ϕ 40th Ave and 1.0' S of Byron Road
Found PK nail in W'ly sde P. Pole N26°E 61.55'
NW cor house S41°E 86.09'
NE cor gas station corner S42°W 103.71'

Accepted as a careful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Corner common to Sections 17, 18, 19 and 20
3" Cast iron monument in monument box (6" below top of box)
3' West of ϕ 40th Ave and 1.0' South of Byron Road
Set nail & O.C. tag in W'ly sde P. Pole N26°E 61.55'
Set nail & O.C. tag in E sde P. Pole S34°E 45.59'
NW cor hse # 3996 S41°E 86.09'
NE cor gas station S42°W 103.71'
SE cor block bldg. N60°W 97.95'



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date October 20, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1988
REVISED MAY 14, 1991
REVISED JAN., 1995