

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:51

COMMISSION

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	Jamestown Township	
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>C-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Deputy Clerk
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Rodney D. Unema, in a field survey on Dec. 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9 Corner Common to Sections 19, 20, 29 and 30	L.C.R.C. Liber 2, Pg. 33	L.C.R.C. Liber 3, Pg. 142
Original gov't corner set in	Feb. 16, 1973	Jan. 3, 1977
Dec. 1831 by Sylvester Sibley	Found 3/4" steel bar	PK in sde T.Pole NW 42.78'
Set post	P.Pole & T.Pole NW 42.45'	PK in sde T.Pole SE 44.03'
Beech 12" N52°E 20 links	P.Pole NE 60.91'	PK in sde P.Pole ENE 61.43'
Beech 10" S55°W 15 links	T.Pole SE 33.70'	Nail in sde 30" Maple NNE 73.43'
	P.Pole SW 47.28'	C/L st. sign SE 38.9'
	C/L st. sign SE	

CONTINUED OVER--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Found C.I.M. in Mon. Box in B.T. at intersection of 40th Ave. and Perry St.	
Found nail & bottle cap in SW sde P.Pole wires N-S-E-W	N70°E 61.0'
Found PK nail in SW sde P.Pole wires N-S	S38°E 51.17'
Found PK nail in SW sde P.Pole wires E-W-S	N70°W 42.78'
Found PK in NW sde P.Pole wires N-S-E-W	N70°E 61.51'

Accepted as a careful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
 PEER APPROVED *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 Corner common to Sections 19, 20, 29 and 30	
Cast Iron Mon. in Mon. Box at intersection of 40th Ave. and Perry St.	
Set nail & O.C. tag in W'yly sde of 30" Maple	N21°E 89.21'
Set nail & O.C. tag in SE sde of P.Pole	N70°E 61.45'
Set nail & O.C. tag in SW sde of P.Pole	S38°E 51.17'
Set nail & O.C. tag in SW sde of P.Pole	N70°W 42.78'
Physical C/L "X" 40th Ave. and Perry St. 5' West and 6' South	



Signed by Rodney D. Unema
 Surveyor's Michigan License No. 33987

Date DEC. 12, 1994

L.C.R.C. Liber 5, Pg. 260
Aug. 28, 1986
Set C.I.M.
PK in T.P. NW 42.78'
PK in P.P. ENE 61.43'
T.P. SE 33.98'
P and T Pole NW 42.78'
30" Maple NE 73.55'

1986
AUG 28
1986