

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE 96 DEC 18 PM 4:51
 Filing Requirement of Act 74, Mich. P.A. 1970

Phyllis Callman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in
 Ottawa
 (County)

Located in: Jamestown Twp. Corner Code # C-10, E1/4 cor.
5N 13W

1. Public Land Survey
 T R Sec. 30
 T R
 T R
 T R

2. Property Controlling
 in Section
 S T R
 S T R

3. Miscellaneous
 Property in Sec.
 S T R
 S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Randal D. Feenstra, in a field survey on Sept 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Hardwood Post	L-3, P 251 1" Iron in Gravel Rd.	W	22.45'
Lucius Lyons, (1832)	Nail in side 14" Oak	SW	27.10'
8" Elm 83°E 19 lks	Pk in top 6" Stump	SE	47.06'
8" Beech N29°W 27 lks	Nail in side 3" Maple Clump	NE	51.96'
	Nail in side 8" Ash		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found: 1" Rnd. Iron in Monument Box on Centerline Paved Road
 Measurement from C-9 to C-10 = 2643.64'
 Measurement from C-10 to C-11 = 2635.73'
 Rerod - 33.00 feet East per recorded survey - L-6, P-685

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12-9-96
R.D.F.

Accepted as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 Set Ottawa County Remon Bar and Cap	Az.	104°	26.17'
Pk and Ottawa County Remon Tag N end 24" CMP	Az.	167°	139.08'
Centerline H.P. Gasline Marker	Az.	191°	156.30'
Nail in Ottawa County Remon Tag E side P. Pole	Az.	321°	55.96'
Nail in Ottawa County Remon Tag NE side 10" Poplar			
On Centerline N/S Bit. Road (40th Ave.)			
Capped Rerod 33.00'E			



Signed by *Randal D. Feenstra*
 Surveyor's Michigan License No. 37275

Date October 10, 1996