

RECORDED

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JUL 24 PM 2: 24

Phyllis Kallman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 5N R 13W C-13 (SE, 31)
 T _____ R _____ Jamestown Twp.
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on April 4, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13 GLO, 1831 CP Co., 1976 Card
 Lucius Lyon, DS Fnd. rebar As wit. as
 Elm 9 corner PP S 80° E 28.80' CP Co.
 Secs. 31-32 TP N 65° W 69.91'
 Rd. sign N 50° W 66.63'

L891, P151, Allegan Co.
 Aug., 1976 CP Co. Survey

Survey K. VanOrder
 1994
 1/2" rerod NE 6,
 4-13
 Ottawa Co. cor. W
 38.91'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found 1/2" capped rerod on C/L road North extended South
 On fence & brush row West
 On Power poles West
 Meas. West 2628.18' to S 1/4 31 (CP Co. 2628.08')
 Meas. East 2653.92' to S 1/4 32 (CP Co. 2653.75')

And is accepted as a careful and faithful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY
 PEER APPROVED 4/21/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Replaced rerod with Ottawa Co. Remon. (3/4" x 24" Pin with Alum. Cap)
 Nail & Ottawa Co. Remon. Tag in N side PP S 80° W 34.70'
 Nail & Ottawa Co. Remon. Tag in W side PP S 10° E 245.86'
 Nail & Ottawa Co. Remon. Tag in N side PP S 85° E 67.03'
 Nail & Ottawa Co. Remon. Tag in W side PP N 03° E 258.63'
 Allegan Co. Mon. (NE 6, 4-13) East 38.92'
 SW cor. trailer (3' above ground) S 60° E 129.00'
 On C/L gravel road North extended South
 C.L CP Towers E-W North 275'±



Signed by John C. Bueche
 John C. Bueche, P.S.
 Surveyor's Michigan License No. 13027

Date 5-29-97