

1993  
COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:30

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Rodney D. Unema, in a field survey on December 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-5 Corner Common to Sections 8, 9, 16 and 17  
L.C.R.C., Liber 2, Page 293 (Aug. 73)  
RR spike in Mon. Box  
PK in sde T.P. NW 62.78'  
MSHD tag in sde T.P. NE 54.21'  
MSHD tag in sde guy pole SE 66.35'  
Nail in sd PP SW 61.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Found RR spike in Mon. Box at intersection of 32nd Ave. and Riley St.  
Found nail & bottle cap in NW sde P.Pole S46°W 61.49'  
Found PK nail in E'ly sde P.Pole N12°W 160.28'  
No other witnesses remaining.  
Accepted position of RR spike as a careful perpetuation of the position of the original corner and replaced RR spike with Std. O.C. Cap on a 3/4" x 24" iron bar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 Corner common to Sections 8, 9, 16 and 17  
Std. O.C. Cap on 3/4" x 24" iron bar in Mon. Box at intersection of 32nd Ave. and Riley St.  
Set nail & O.C. tag in E'ly sde of Pole S46°W 61.39'  
Set nail & O.C. tag in E'ly sde of P.Pole N12°W 160.38'  
Set nail & O.C. tag in NW sde of guy pole N53°E 73.03'  
SW cor block bldg. S32°E 107.30'

Signed by Rodney D. Unema  
Surveyor's Michigan License No. 33987

Date December 6, 1993

