

**SURVEY &
REMONUMENTATION**

OTTAWA COUNTY REMONUMENTATION

RECORDED

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE 94 DEC -8 PM 12:30

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Richard Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located in: Jamestown Township	Corner Code ## E-11
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Rodney D. Unema in a field survey on Nov. 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11 Corner Common to Sections 28, 29, 32 and 33	L.C.R.C. Liber 3, Page 43	L.C.R.C. Liber 5, Page 189
Original gov't corner set in Dec. 1831 by Sylvester Sibley	(March 22, 1976)	(Dec. 27, 1984)
Set post	Found iron in Mon. Box	Set cast iron Mon.
Sugar 14" S79°W 10 links	PK in sde P.Pole SW 68.03'	34" Ash NW 69.08'
Ironwood 5" N10°E 7 links	Nail in sde 26" Ash NW 68.47'	P.Pole SW 67.77'
	Center street sign SE 35.8'	Street sign SE 36.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11
Found 3" cast iron Mon. in Mon. Box at intersection of Adams St. and 32nd Ave.
Found sq. spike in E side 36" Ash N27°W 68.55'
Found PK nail in NW side power pole S35°W 67.75'
Center of street sign S40°E 36.77'

Accepted as a careful perpetuation of the position of the original corner.


PA. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Corner Common to Sections 28, 29, 32 and 33
3" dia. cast iron Mon. in Mon. Box in blacktop at C/L "X" of Adams St. and 32nd Ave.
Set nail & O.C. tag in E side 36" Ash N27°W 68.55'
Set nail & O.C. tag in NW side P.Pole S35°W 67.75'
Cut "X" in N end of 24" conc. culv. N63°E 59.94'
Cut "X" in S end of 24" conc. culv. S30°E 60.95'



Signed by Rodney D. Unema

Date Nov. 18, 1994

Surveyor's Michigan License No. 33987