

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:30

For corners in **COMMISSION**
 Ottawa

Edyella Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

	Located In:	Corner Code #
	Jamestown Township	E-12
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on Nov. 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12 1/4 Corner Between Sections 32 and 33	L.C.R.C. Liber 1, Page 147	L.C.R.C. Liber 4, Pg. 160
Original gov't corner set in Dec. 1831, by Sylvester Sibley	(Nov. 23, 1971)	(April 1, 1981)
Set H.W.P.	Steel bolt in bridge deck	Set cast iron Mon.
B. Ash 20" S41°W 28 links	Nail in face of T.pole SE 70.10'	Street sign WNW 28.00'
Elm 10" S60°E 31 links	Nail in face of P.Pole NW 51.40'	Power pole SW 59.54'
	Nail in face of T.pole NE 58.25'	Con. conc. culv. SE 28.90'
	C/L street sign SW 28.95'	C/L gravel road West 5.0'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12
 Found 4" cast iron Mon. in Mon. Box (10" below top)
 At "T" intersection of 32nd Ave. and Mason St.
 Found PK nail & washer in NW side P.Pole
 Found nail in NE side twin 20" Basswood

S65°W 59.53'
 N38°W 116.95'

Accepted as a careful perpetuation of the position of the original corner, and placed Std. O.C. cap on 7" x 3/4" iron bar in grout over top of existing cast iron Mon. in Mon. Box.

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 1/4 Corner between Sections 32 and 33
 Std. O.C. cap on 7" x 3/4" iron bar in grout over top of existing cast iron Mon. in Mon. Box
 Set nail & O.C. tag in NE side twin 20" Basswood
 Set nail & O.C. tag in N end 18" CMP culv.
 Set nail & O.C. tag in S end 18" CMP culv.
 Set nail & O.C. tag in NW side P.Pole
 C/L N-S B.T. road (32nd Street)
 C/L gravel road to East (Mason St.)

N38°W 116.95'
 N56°E 37.35'
 S47°E 42.12'
 S65°W 59.53'
 West 7.0'
 South 3.5'

Rodney D. Unema

Signed by Rodney D. Unema
 Surveyor's Michigan License No. 33987

Date Nov. 18, 1994

