

**SURVEY &  
REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:30

For corners in **COMMISSION**

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
	Jamestown Township	
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>F-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Rodney D. Unema*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on Nov. 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-11 1/4 Corner Between Sections 28 and 33		
Original gov't corner set in	L.C.R.C. Liber 4, Page 23	L.C.R.C. Liber 5, Page 190
Dec. 1831 by Sylvester Sibley	(Jan. 23, 1980)	(Dec. 27, 1984)
Set 1/4 Section post	1" iron in Mon. Box	Set Cast Iron Mon.
Beech 12" S76°E 4 links	C/L street sign SE 42.6'	Power pole SW 82.54'
Beech 4" N41°W 19 links	PK on side P.Pole SW 82.2'	Power pole NW 116.12'
	Nail in face P.Pole NW 116.1'	Street sign SE 42.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11  
Found Cast Iron Mon. in Mon. Box (top broken off) 6" below B.T. road surface at C/L intersection of 28th and Adams.  
Found small PK in NW side of P.Pole wires N, S, E & W S45°W 82.51'  
Found P.Pole (no nail) wires N-S N25°W 116.10'  
Found street sign leaning E-SE S35°E 42.52'  
Found PK in S side of 6"x6" fence post N50°E 47.17'

Accepted center of cast iron Mon. as a careful perpetuation of the original corner.

*Rodney D. Unema*  
P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 1/4 Corner Between Sections 28 and 33	
Center of Cast Iron Mon. (top broken off) in Mon. Box at C/L "X" of Adams Street & 28th Ave.	
Set O.C. nail & tag in NW'ly side of P.Pole wires N, S, E & W	S45°W 82.51'
Set O.C. nail & tag in E'ly side of P.Pole wires N-S	N25°W 116.42'
Corner of brick at grade level at SW corner of house #2780	S25°E 167.60'
Set O.C. nail & tag in S side of 6" x 6" fence post	N50°E 47.17'

Signed by Rodney D. Unema  
Surveyor's Michigan License No. 33987

Date Nov. 21, 1994

