

OCT 24 1994

COMMIS.

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 OCT -7 PM 12:33

For corners in

Ottawa

(County)

Located in:

Jamestown Township

Corner Code #/

1. Public Land Survey	T	5N	R	13W	G-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Rodney D. Unema
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Rodney D. Unema, in a field survey on September 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7 Corner Common to Sections 15, 16, 21 and 22
Original gov't corner set in Dec. 1831
by Sylvester Sibley
Set post
Beech 20" N68°W 10 links
Sugar 7" S51°E 21 links

L.C.R.C. Liber 1, Page 451
(June 1972)
Mon. Box @ corner
Nail in side P.Pole NE 53.94'
Nail in side P.Pole NW 63.14'
Nail in side P.Pole SSW 75.02'
Nail in side Utility Pole SSE 78.35'

L.C.R.C. Liber 5, Page 18
(Dec. 1984)
Cast iron monument
P.Pole NW 54.05'
P.Pole NW 63.07'
P.Pole SE 78.24'
P.Pole SW 101.62'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7
Found C.I.M. in mon. box (8" below top of mon. box)
Found PK in SE side of P.Pole N33°E 54.06'
Found PK in W side of P.Pole S16°E 78.42'
Found bent nail in N side guy pole S76°W 101.66'
Found PK in SW side of P.Pole N42°W 63.08'

* Accepted as a careful perpetuation of the position of the original corner.


P.A. 345 OTTAWA COUNTY

PEER APPROVED 9/19/94

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 Corner Common to Sections 15, 16, 21 and 22
3" dia. cast iron mon. in mon. box (8" below top of mon. box)
at C/L "X" of Byron Road and 24th Avenue
Set nail & O.C. tag in SE side P.Pole N33°E 54.06'
Set nail & O.C. tag in W side P.Pole S16°E 78.45'
Set nail & O.C. tag in N side guy pole S76°W 101.66'
Set nail & O.C. tag in SW side P.Pole N42°W 63.10'
Set nail & O.C. tag in curb joint N44°W 44.04'



Signed by Rodney D. Unema

Date September 19, 1994

Surveyor's Michigan License No. 33987