

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:45

Rhonda Anderson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa
 (County)

Located In:
 Jamestown Township

Corner Code #:

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>5N</u> R <u>13W</u> | <u>G-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Rodney D. Unema, in a field survey on Nov. 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-10 1/4 Corner Between Sections 27 and 28

Original gov't corner set in Dec. 1831
 by Sylvester Sibley
 Set H.W.P.

B. Ash 10" N79°W 28 links
 B. Ash 12" S66°E 36 links

L.C.R.C. Liber 5, Page 194 (Jan. 16, 1985)
 RR Spike
 Nail in NW sde guard post N20°E 97.62'
 Nail in NE sde guard post N20°W 109.15'
 Nail in NW sde 5" Ash N40°E 46.81'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 Found RR spike in B.T. on C/L on N-S Road (24th Ave.)
 Center of 10" Ash N39°E 46.82'
 No other witnesses remaining

Accepted as a careful perpetuation of the position of the original corner, and replaced RR spike with Std. O.C. Cap on 24" x 3/4" iron bar in new Mon. Box.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate the position of the corner:

G-10 1/4 Corner Between Sections 27 and 28
 Std. O.C. Cap on 3/4" x 24" Iron Bar in Mon. Box
 Cut "X" on W end of 48" conc. culvert
 Cut "X" on E end of 48" conc. culvert
 Set nail & O.C. tag in NW sde 10" Ash
 Set nail & O.C. tag in SW sde 5" Elm
 On C/L of N-S BT Road (24th Ave.)

N14°W 105.96'
 N15°E 107.49'
 N39°E 46.82'
 S32°E 75.26'



Signed by Rodney D. Unema

Date DEC. 12, 1994

Surveyor's Michigan License No. 33987