

**Ottawa County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

97 JUL 24 PM 2:24

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

- |                                       |                          |                       |
|---------------------------------------|--------------------------|-----------------------|
| 1. Public Land Survey                 | T <u>5N</u> R <u>13W</u> | <u>G-13 (SE, 33)</u>  |
|                                       | T _____ R _____          | <u>Jamestown Twp.</u> |
|                                       | T _____ R _____          | _____                 |
|                                       | T _____ R _____          | _____                 |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____                 |
|                                       | S _____ T _____ R _____  | _____                 |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____                 |
|                                       | S _____ T _____ R _____  | _____                 |
| 4. Lot No. _____, Recorded Plat _____ |                          |                       |
| 5. Private Claims _____               |                          |                       |

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on April 15, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13 GLO, 1831	L882, P658 Allegan Co.
Lucius Lyon, DS	Aug., 1976 CP Co. Survey
Set post cor.	
Secs. 33 & 34	Shows dist.; jog of 83.45'
Sugar 7 N 60 E 7	at SW 34
Beech 6 N 59 W 21	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found 3/4" pipe on C/L gravel road E-W; C/L bit. extended South is 1.5'± East of cor.  
 Meas. West to S 1/4 33 2659.32' (CP comp. 2659.38')  
 Meas. East to S 1/4 34 2659.56' (CP comp. 2659.56')  
 NE cor. 4, 4-13 East 83.48' (GLO 63.36')

And is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 4/21/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Replaced 3/4" pipe with Ottawa Co. Mon. (3/4" x 24" Pin with Alum. Cap)  
 Nail & Ottawa Co. Remon. Tag in NW side 26" Maple S 65° W 113.48'  
 Nail & Ottawa Co. Remon. Tag in NE side PP N 3° W 72.32'  
 Nail & Ottawa Co. Remon. Tag in W side 8" Elm N 0° E 73.78'  
 SE cor. hse. fnd. S 35° W 136.27'  
 Nail & Ottawa Co. Remon. Tag in S side PP N 64° E 154.68'  
 On C/L gravel road E-W  
 Allegan Co. Mon. NE 4, 4-13 East 83.48' (iron in mon. box is North 1.24' of corner on South line of Township)

Signed by John C. Bueche  
 John C. Bueche, P.S. 13027  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 5-29-97

