

SURVEY & REMONUMENTATION

FEB 27 1998

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 DEC -8 AM 11:32

Randy Sublett
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

For corners in
SECTION
OTTAWA
(County)

Located in: Corner Code #

| | | |
|---------------------------------------|--|-------------------------------|
| 1. Public Land Survey | T <u>5N</u> R <u>13W</u> | H-7 (N 1/4 corner Sec. 22) |
| | T <u> </u> R <u> </u> | Jamestown |
| | T <u> </u> R <u> </u> | Township <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | |
| | S <u> </u> T <u> </u> R <u> </u> | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, Randal J. Vugteveen, in a field survey on December 5, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7 Common corner to Sections 15 & 22
1831 - Lyon
Set post on true line
20" Beech N38° W 25 Links
7" Sugar S27° E 19 Links

Liber 6 Page 171
Set CIM
PK nail in t. pole SE 112.10'
T. pole SSW 26.24'
9" Ash NNW 40.61'
10" Willow NE 70.78'

Liber 4 Page 101
Center Byron Road N. 3.5'
PK in side power pole ESE 112.03'
PK in N side power pole WSW 191.81'
PK in side power pole SW 26.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found broken CIM 1' down in monument box on tree line to South

Telephone pole SSW 26.26'
Centerline Byron Road North 3.5'

Accepted position of cast iron monument as a careful perpetuation of the position of the original corner

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/1/97

RJV

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 - Cast Iron Monument in Monument Box

Found Ottawa County Remon tag & nail in North side power pole AZ 105° 112.04'
Found Ottawa County Remon tag & nail in East side power pole AZ 215° 26.26'
Found Ottawa County tag & nail in North side power pole AZ 265° 191.72'
Centerline Byron Road North 3.5'



\$ 9.00 CORNER
\$ 1.00 PHOTO

Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date Dec 1, 1997