

**SURVEY &
REMONUMENTATION**

NOV 10 1993

COMMISSION

OTTAWA COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa <small>(County)</small>	Located In:	Corner Code #
	Jamestown Twp.	
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>I-3 NW cor.</u>
	T _____ R _____	<u>Section 11</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECORDED
1993 SEP 29 PM 3:14
Phyllis Johnson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3									●				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Rodney D. Unema, in a field survey on July 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-3 Section Corner 2, 3, 10, 11

L.C.R.C. Liber 1, Page 301 (1972)

3/4" I.P. inside 2" I.P.

Nail in side of 20" Maple E-SE 108.9'

Nail in side of 18" Ash E-NE 72.5'

Nail in side of 4" Maple SW 86.5'

Center of street sign N-NE 13.85'

L.C.R.C. Liber 2, Page 683 (1974)

Iron pipe

Nail in side 18" Ash E-NE 72.64'

Nail in side 24" Maple E-SE 109.55'

Nail in side 12" Maple cluster E-SE 86.48'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found 1" I.P. inside 2"x36" long I.P. at intersection of 16th Avenue and Quincy Street.

Found nail & tag in S side 18" Ash N77°E 72.68'

Found nail & tag in N side Maple clump S67°E 86.44'

Found nail & tag in N side 30" Maple S76°E 108.95'

Found nail in E side 16" Ash S18°W 142.10'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Corner Common to Sections 2, 3, 10 and 11

Replace I.P.'s with Std. O.C. cap on 36" iron. Accepted as a careful perpetuation of the position of the original corner.

On C/L of 16th Avenue (B.T.) to South

North edge of Quincy Street (gravel) North 4.0'

Nail & O.C. tag in S side 20" Ash N77°E 72.67'

Nail & O.C. tag in N side 30" Maple S76°E 109.38'

Nail & O.C. tag in E side 16" Ash S18°W 142.07'

Nail & O.C. tag in E side 16" Maple N19°W 116.39'

Signed by Rodney D. Unema Date September 20, 1993
Surveyor's Michigan License No. 33987