

SURVEY & REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OTTAWA

(County)

Located In:

Corner Code #

Jamestown Township

- | | | | | | |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 5N | R | 13W | I-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |

RECORDED

95 NOV 15 PM 2:10

Sylvester Sibley
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Rodney D. Unema, in a field survey on October 12, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-9 corner common to Sections 22, 23, 26 and 27
Dec.1831 original gov't corner set by Sylvester Sibley
Set Post
6" B. Oak N22°W 21 links
8" Butternut S2°E 16 links

LCRC Lib 3, Pg 165 (5/77)
Set solid rod
PK in sde guy pole WNW 151.71'
PK in sde P Pole NNE 133.80'
PK in sde P. Pole SE 61.71'
Cor fe post (steel) SW 41.95'

LCRC Lib 3, Pg 314 (1/79)
Found steel bar
PP SE 61.68'
¢ street sign SW 38.25'
Iron fence cor SW 41.96'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-9 Found solid bar (6" below gravel) on ¢ of Perry Street and 16th Avenue
Found PK nail in W'ly sde P. Pole N23°E 133.54'
Found PK nail in NE sde P. Pole S41°E 61.69'
Found PK nail in S sde P. Pole N77°W 151.69'
¢ street sign S54°W 38.17'

Accepted solid bar as position of corner and replaced with standard Ottawa County Remon. cap and 3/4" x 24" bar.


P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95 RDU

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Corner common to Sections 22, 23, 26 and 27
OC remon cap on 3/4" x 24" bar (8" below gravel) on ¢ of Perry Street & 16th Avenue
Set nail & OC tag in W'ly sde P. Pole N23°E 133.54'
Set nail & OC tag in NE sde P. Pole S41°E 61.69'
Set nail & OC tag in S sde P. Pole N77°W 151.68'
¢ street sign S54°W 38.17'
NW cor 2.0' x 6.0' stone base of Hilzey mon S23°W 280.11'
(0.7' above ground)



Signed by Rodney D. Unema

Date October 20, 1995

Surveyor's Michigan License No. 33987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983