

**SURVEY &  
REMONUMENTATION**

APR 05 1996

**COMMISSION**

OTTAWA COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OTTAWA <small>(County)</small>	Located In:	Corner Code #
	Jamestown Township	
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>I-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECORDED**

95 NOV 15 PM 2:09

*Phyllis Kellman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on October 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-10 1/4 corner between Sections 26 and 27  
Dec. 1831 original gov't corner LCRC Lib 5, Pg 194 (1/85)  
set by Sylvester Sibbey Set capped iron base on  
Set H.W.P. 1964 information of Williams  
8" Lyme S77°W 36 links & Works  
6" Butternut N10°E 41 links PK in NW sde guy pole S75°W 28.35'  
PK in SW sde T. Pole S35°E 28.95'  
Nail in N sde 28" Ash S75°E 59.58'  
Nail in NE sde Tw. 8" Ash N45°W 42.50'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-10 Found capped iron  
Found PK in SW sde T. Pole East 1.0'  
Found nail in N sde 30" Ash S29°E 30.28'  
Found Ash stump S72°E 59.58'  
N41°W 42.7'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

*Rodney D. Unema*  
RDU

Accepted as a careful perpetuation of the position of the original corner and replaced iron with standard Ottawa County remon cap on 3/4" x 24" iron bar.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-10 1/4 corner between Sections 26 and 27  
Standard O.C. Remon cap on 3/4" x 24" bar (8" below gravel surface)  
Set nail & OC tag in SW sde T. Pole S29°E 30.28'  
Set nail & OC tag in N sde 30" Ash S72°E 59.58'  
"X" in top of N end 48" conc culvert S53°W 28.71'  
Set nail & OC tag in W sde P. Pole N25°E 111.33'  
of 16th Avenue East 1.0'



Signed by Rodney D. Unema  
Surveyor's Michigan License No. 33987

Date October 20, 1995