

**SURVEY &
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

95 NOV 15 PM 2: 09

Rodney D. Unema
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

For corners in **COMMISSION**

OTTAWA
(County)

Located In: Jamestown Township Corner Code I-11

1. Public Land Survey	T	5N	R	13W	I-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Rodney D. Unema, in a field survey on October 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Corner common to Sections 26, 27, 34 and 35	LCRC Liber 1, Pg 635 (9/72)	LCRC Lib 5, Pg 190 (12/84)
Dec, 1831 original govt corner set by Sylvester Sibley	Found 1" pipe	Set C.I.M.
Set post	NW PP 82.64'	PP SW 37.44'
12" Beech S65°E 13 links	S 15" Willow 41.98'	St. sign SE 44.40'
16" Sugar N31°W 14 links	ENE Culv. post 69.95'	PP NE 89.42'
		TP NW 48.96'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found 4" diameter cast iron monument in monument box (3" below top of box)
Mon. is on ϕ "X" of 16th Avenue and Adams Street
Found nail in S sde P. Pole N70°E 89.42'
St. sign S30°E 44.4'
Found nail in SW sde P. Pole S42°W 37.44'

Accepted as a careful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Corner common to Sections 26, 27, 34 and 35
4" diameter cast iron monument in monument box (3" below top of box)
Monument is on ϕ "X" of 16th Avenue and Adams Street
Set nail & OC tag in S sde P. Pole N70°E 89.43'
Set nail & OC tag in SW sde P. Pole S42°W 37.44'
Set nail & OC tag in E sde 10" Maple N22°W 76.62'
SW cor of House # 825 (to siding) N45°W 175.32'



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date October 20, 1995