

**SURVEY &
REMONUMENTATION**

NOV 10 1993

OTTAWA COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa
(County)

Located In:

Corner Code #

Jamestown Twp.

1. Public Land Survey

T 5N R 13W

J-3 N 1/4 cor.

T _____ R _____

Section 11

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED

1993 SEP 29 PM 3:14

Reggie S. Johnson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on July 28, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-3 1/4 Corner Between Sections 2 and 11

L.C.R.C. Liber 3, Page 142 (1976)

1/2" solid rod

Nail in side 54" Ash W-NW 91.25'

PK nail in side T.Pole South 36.22'

NW cor gar. fndn. SW 99.96'

L.C.R.C. Liber 5, Page 44 (1983)

Capped Re-rod

Nail in NE side 6" W. Ch. NW 54.04'

PK in top wood fe. post SE 68.23'

SW cor house NE 97.06'

PK in E side P.Pole South 36.26'

NW cor gar. fndn. SW 100.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found rebar in pavement at intersection of 12th Avenue and Quincy Street

Found nail & tag in E side P.Pole S05°W 36.04'

Found scar in NE side 12" W. Cherry N35°W 54.0'

SW cor house N48°E 97.04'

Found PK nail in top of fence post S58°E 68.31'

NW cor gar. fndn. S41°W 100.08'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 1/4 Corner Between Sections 2 and 11

Replaced rebar with Std. O.C. cap on 24" iron bar. Encased in concrete flush with pavement. Accepted as a careful perpetuation of the position of the original corner.

On C/L of 12th Avenue to North / C/L of Quincy Street (B.T.) is North 1.0'

Nail & O.C. tag in NE side of 12" W. Cherry N35°W 54.13'

Nail & O.C. tag in E side P.Pole S05°W 35.93'

Nail & O.C. tag in SW side fe. post S58°E 68.16'

SW cor. house (brick) N58°E 97.04'

NW cor. gar. fndn. S41°W 100.08'

Signed by

Rodney D. Unema

Date September 20, 1993

Surveyor's Michigan License No. 33987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983