

SURVEY & REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
OTTAWA

(County)

Located In: Corner Code #
Jamestown Township

| | | | | | |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 5N | R | 13W | J-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

RECORDED

95 NOV 15 PM 2:09

Dorothy Erdman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Rodney D. Unema, in a field survey on October 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9 1/4 corner between Sections 23 and 26
Dec. 1831, original gov't corner LCRC Liber 3, Pg 314 (1/79)
set by Sylvester Sibley Found "T" iron
Set 1/4 Sec. post PP SE 89.51'
4" Hickory S25°E 23 links TP WNW 160.98'
6" Sugar N45°E 31 links PP WSW 174.23'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 Found "T" iron (6" below gravel)
¢ of Perry Street South 7'
Found PK nail in N sde P. Pole S55°E 89.59'
Found PK nail in S sde T. Pole N80°W 160.94'
Found PK nail in N sde P. Pole S77°W 174.26'

Accepted as a careful perpetuation of the position of the original corner and replaced with standard Ottawa County Remon. cap on 3/4" x 24" iron bar.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 1/4 corner common to Sections 23 and 26
OC Remon cap on 3/4" x 24" bar (6" below gravel)
¢ Perry Street (gravel) South 7'
Set nail & OC tag in N sde P. Pole S55°E 89.59'
Set nail & OC tag in S sde T. Pole N80°W 160.93'
Set nail & OC tag in N sde P. Pole S77°W 174.26'
SE cor hse # 1208 (to corner of siding) S30°W 141.85'



Signed by Rodney D. Unema
Surveyor's Michigan License No. 33987

Date October 20, 1995