

DEC 03 1993

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE 93 NOV 11 AM 11:56  
Filing Requirement of Act 74, Mich. P.A. 1970

*Rodney D. Unema*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

Jamestown Township

- |                                    |   |    |   |     |     |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey              | T | 5N | R | 13W | K-3 |
|                                    | T |    | R |     |     |
|                                    | T |    | R |     |     |
|                                    | T |    | R |     |     |
| 2. Property Controlling in Section | S |    | T |     | R   |
|                                    | S |    | T |     | R   |
| 3. Miscellaneous Property in Sec.  | S |    | T |     | R   |
|                                    | S |    | T |     | R   |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Rodney D. Unema, in a field survey on October 22, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3 Corner common to Sections 1, 2, 11 and 12

L.C.R.C. Liber 5, Page 352 (Dec. 1988)

- Cast Iron Mon.
- 28" Maple SE 67.92'
- 28" Maple SSE 80.94'
- PP SSW 147.12'
- 12" Maple SW 49.42'

L.C.R.C. Liber 1, Page 325 (April 1972)

- Iron in Mon. Box
- Nail in sde P.Pole NE 36.20'
- Nail in face 26" Maple SE 66.78'
- Nail in sde 26" Maple SSE 55.0'
- NE cor. porch fndn. SW 117.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found O.C. CI Mon. 2" below pavement surface @ intersection of Quincy St. and 8th Ave.

- Found nail in NE sde of 36" Maple S50°E 67.92'
- Found nail in W sde of 36" Maple S18°E 80.94'
- Found PK nail in W sde of P.Pole S24°W 147.16'

Accepted as a careful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Corner common to Sections 1, 2, 11 and 12

Ottawa Co. Cast Iron Mon. (2" below pavement surface)

On C/L of N-S BT Road (8th Avenue)

C/L of gravel road to East

C/L of BT road to West

- South 4.5'
- North 1.5'
- O.C. tag & nail in SE sde of 12" Maple S45°W 49.30'
- O.C. tag & nail in NE sde of 36" Maple S50°E 68.05'
- O.C. tag & nail in W sde of P.Pole N17°E 115.33'
- O.C. tag & nail in N sde of Service Pole N76°W 145.93'



Signed by Rodney D. Unema

Date November 3, 1993

Surveyor's Michigan License No. 33987