

DEC 01 1993

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV 11 AM 11:56

COMMISSION

For corners in

Ottawa
(County)

Located In: Corner Code #

Jamestown Township

1. Public Land Survey	T	5N	R	13W	K-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Rodney D. Unema, in a field survey on October 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4 1/4 corner between Sections 11 and 12

L.C.R.C. Liber 5, Pg. 349 (Dec. 1988)	L.C.R.C. Liber 2, Pg. 299 (September 1973)	L.C.R.C. Liber 1, Pg. 325 (April 1972)
Cast iron Mon. in Mon. Box.	RR Spike	Iron in Mon. Box
C/L stop sign WSW 43.20'	St. sign N90°E 19.65'	Nail in sde P.Pole SE 62.34'
PP SW 74.22'	CP pole S35°E 62.30'	Nail in sde P.Pole SW 59.49'
PP SE 62.34'	CP/MBT pole S40°W 59.50'	W edge St. sign post E 19.53'
12" Elm E 58.93'		SE cor. barn NW 152.39'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-4 Found Ottawa Co. C.I. Mon. in Mon. Box 2" below pavement at intersection of 8th Avenue and Greenly.
- Found nail in S sde 14" Elm N84°E 58.93'
- Found nail in NE sde P.Pole S34°E 62.22'
- Found PK nail in SE sde P.Pole S45°W 74.28'

Accepted as a careful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-4 1/4 corner between Sections 11 and 12
- O.C. Cast iron Mon. in Mon. Box 2" below pavement surface
- On C/L of N-S BT road (8th Avenue)
- C/L of BT road to West North 3.0'
- O.C. tag & nail in SE sde P.Pole S45°W 74.27'
- O.C. tag & nail in NE sde P.Pole S34°E 62.20'
- O.C. tag & nail in S sde 14" Elm N84°E 58.93'
- C/L 3" dia. street sign pole N28°W 65.78'
- O.C. tag & nail in E sde P.Pole N08°W 259.32' (E.D.M.)



Signed by Rodney D. Unema Date November 4, 1993
Surveyor's Michigan License No. 33987