

DEC 01 1993

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV 11 AM 11:56

Richard Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

Jamestown Township

1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Rodney D. Unema, in a field survey on August 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-5 Corner common to Sections 11, 12, 13 and 14

L.C.R.C. Liber 5, Page 86 (Dec. 1983)

Cast iron Mon.

Power pole SE 71.77'

Street sign SW 52.42'

Fence post NW 48.16'

Fence post NE 78.29'

L.C.R.C. Liber 1, Page 327 (April 1972)

"T" iron

Nail in sde P.Pole SE 71.35'

NE edge St. sign post SW 52.42'

iron at S edge of Stop sign NE 42.11'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5 Found Ottawa Co. cast iron Mon. in Mon. Box at intersection of 8th Ave. and Riley St.

Found nail in NE sde fence post N45°W 48.20'

Found nail in SE sde fence post N27°E 78.05'

C/L street sign post S50°W 52.27'

PK nail in SW sde P.Pole S32°E 71.83'

Accepted as a careful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 Corner common to Sections 11, 12, 13 and 14

Cast iron monument in Mon. Box at intersection of 8th Ave. and Riley St.

O.C. tag & nail in SW sde P.Pole S32°E 71.92'

O.C. tag & nail in SW sde fence post N45°W 48.37'

O.C. tag & nail in E sde of 8" Elm N10°W 140.27'

O.C. tag & nail in SE sde of 14" Maple N60°E 103.34'

Chisled "X" in top of W end conc. culvert S35°W 44.16'



Signed by

Rodney D. Unema

Date

November 4, 1993

Surveyor's Michigan License No. 33987