

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In: Jamestown Township	Corner Code # K-6
1. Public Land Survey	T <u>5N</u> R <u>13W</u>	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
95 NOV 29 PM 1:42
Rodney D. Unema
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, Rodney D. Unema, in a field survey on October 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6 1/4 corner between Sections 13 and 14 Dec., 1831, original govt Corner set by Sylvester Sibley Set H.W.P. 16" Beech 12" Sugar	N86°E 19 links S88°W 50 links	W 69.13' PK nail in N sde P. Pole PK nail in fence post ¢ gravel "L" iron	E 98.00' NE 68.51' E 3.0' E 26.30'	LCRC Lib. 5, Pg 349 (12/88) Set cast iron monument Cor wood fence post NE 56.75 4" Maple 4" Maple 20" Maple	E 43.38 SE 52.86' W 69.09'
--	----------------------------------	---	---	--	----------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found 4" diameter cast iron monument in monument box (8" below top of box)
Monument is 1.5' West of ¢ 8th Avenue
Found PK nail in N side P. Pole S88°E 97.97'
Found nail in S side 22" Walnut N89°W 69.09'

Accepted as a careful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95
Rodney D. Unema

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 1/4 corner between Sections 13 and 14
4" diameter cast iron monument in monument box (8" below top of box)
Set nail and OC tag in N side P. Pole S88°E 97.97'
Set nail and OC tag in SW side 10" Maple S37°E 70.47'
Set nail and OC tag in S side 22" Walnut N89°W 69.07'
Set nail and OC tag in S side P. Pole N70°W 52.44'
¢ of 8th Avenue East 1.5'



Signed by Rodney D. Unema Date November 20, 1995
Surveyor's Michigan License No. 33987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, REVISED MAY 14, REVISED JAN.